BANGALORE DIVISION.

Dated 11th May 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 4 P.M., on Tuesday the 4th June 1918, for constructing "Out-patients' Dispensary outside the compound of Victoria Hospital, Bangalore." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,500 (one thousand and five hundred) in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing an Out-patients' Dispensary, outside the compound of Victoria Hospital at Bangalore," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer of Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates quoted must be specific. Tenders with vague quotations such as "as per market" will be rejected.

Abstract quantity for constructing Out-patients' Dispensary at Victoria Hospital, Bangalore.

No.	Details of works	Per	Rate	Quantity	Cost
			Rs. a. p.		Rs. a. p.
1	Earthwork excavation and filling basement ...	C. yd.	.....	724	
2	Filling foundation with concrete	C. ft.	.....	7,277	
3	Stone in mortar, foundation and basement (basement one line dressed).	"	.....	15,022	
4	Superstructure burnt stone in mortar with bond stones including corner dressing, etc.	"	.....	21,621	
5	Arch work cut stone in mortar exposed faces, 2 line dressed.	"	.....	1,006	
6	Burnt stone slabs dressed roughly, wherever necessary (4" to 6").	S. ft.	.....	4,366	
7	Burnt stone slabs, 2 lines dressing only	"	.....	2,443	
8	Plastering with chunam	Sq.	.....	168·93	
9	Cement pointing with lining	"	.....	133·75	
10	Whitewashing, 2 coats	"	.....	168·93	
11	Flooring with 1½" patent stone over 4½" lime and stone concrete.	"	.....	81·65	
12	Flooring with Cuddappah slabs over 4" concrete bed and cement pointing.	"	.....	16·20	
13	Pucca terrace	"	.....	50·30	
14	Roofing with 1st class Mangalore tiles with asbestos sheet ceiling teak reepers and complete.	"	.....	43·59	
15	Roofing with 1st class Mangalore tiles without ceiling ...	"	.....	15·44	
16	Ridge tiles set in mortar and pointed with cement ...	R. ft.	.....	270	
17	Teakwood work including wood oiling	C. ft.	.....	1,155·69	
18	Teakwood panelled doors with frame brass fittings, etc., complete.	S. ft.	.....	1,021	
19	Teakwood windows with panelled shutters outside and glazed inside with iron bars.	"	.....	954	
20	Teakwood ventilators, glazed	"	.....	150	
21	Teakwood circular ventilators	"	.....	304	
22	Teakwood almirahs with glazed shutters, etc. ...	"	.....	120	
23	Ornamental cave boards 8" including painting ...	R. ft.	.....	309	
24	Rain water pipes 3" diameter	"	.....	250	
25	Ornamental balustrade parapet wall with finials, etc., complete.	"	.....	322	
26	Parapet wall ordinary with cement plastering and finials...	"	.....	225	
27	Cornice with cement plastering	"	.....	870	
28	Cut stone pillars with base and capital (8'×7½"×7½") ...	Each	.....	18	
29	Cut stone round pillars 1' dia. with stone base and capitals	"	.....	18	
30	Double half pillars at corners of tower with base, complete.	"	.....	8	
31	Stone binding wall above gable including finials ...	R. ft.	.....	140	
32	Teakwood screen including painting	S. ft.	.....	510	
33	Silicate painting, 2 coats	Sq.	.....	57·78	
34	Teakwood tresses with iron fittings, brackets, painting for 25 feet span.	Each	.....	4	
35	Teakwood tresses with brackets for 20 feet span including iron works.	"	.....	4	
36	3" stoneware pipes	R. ft.	.....	20	
37	Wooden ladder with iron fittings, painting, etc. ...	Each	.....	1	

C. VIJIYARANGAM NAIDU, *Executive Engineer.*

4 C